

Super-Slab® Precast Pavement System

FORT MILLER
THE FORT MILLER CO., INC.



*Precast Concrete
Solutions*

The Fort Miller Co., Inc.

Dan E. Moellman, P.E.

Precast Concrete Pavement Slabs = Overnight Repairs



145,000 ADT
I-287, Tarrytown, NY




200,000 ADT
I-15, Ontario, CA



180,000 ADT
I-66, Fairfax, VA

Precast Pavement Emulates Cast in Place



Precast Equivalent

- Full Bedding Support
- Load transfer Dowels
- Slab Surface Geometry






Current Precast Systems

- **Precast Prestressed Concrete Pavement (PPCP)**
 - Pre & post tensioned (250'± assembly)
 - Developed by FHWA (non-proprietary)
- **Top-Slot Jointed Systems (Michigan Method)**
 - Jointed – slab lengths 16' ± long
 - Developed by FHWA (non-proprietary)
 - Flowable fill or urethane foam support
- **Bottom-Slot Jointed System (Super-Slab®)**
 - Jointed – slabs 6' to 16'
 - Grade supported
- **Other systems are “appearing”**

Bottom-Slot Super-Slab® System (Proprietary)



- Simple slab-on-grade system
- Standard dowels and tie bars (JRCP)
- Built-in bedding grout distribution
- Precision grading equipment
- Warped and planar surfaces
- 10,000 slabs = 1,000,000 SF INSTALLED



**(48 projects, 20 lane-miles completed in 9 States + ONT & QUE)
(Over 95% of all jointed precast in US)**



Super-Slab® Load Transfer Dowel System

- Dowels engage slots in adjacent slab
- Pump dowel group into ports
 - Grout reaches 2500 psi in about 2 hours
- Fill slots and joint between slabs
- Dove-tail slot resists bar pop out
- Proprietary detail




Dove-tail-shaped slot




Two Types of Slabs

Slab shape depends on geometry of pavement surface

Single Plane



Warped Plane



Warped Super-Slab® panels are proprietary to The Fort Miller Co., Inc.

Intermittent Repairs (CPR)



**I- 90
Albany, NY**



**I-676 Vine St
Expressway
Philadelphia,
PA**




**I-15 Salt Lake
City, Utah**



I-95, New Rochelle, NY

Continuous Mainline - Tappan Zee Bridge Toll Plaza



This

(3,000 SF Per Eight Hour Shift)

(Within \pm 3 mm)

In 2001 and 2002



While Maintaining

This

(135,000 Vehicles per Day)



Mainline Interstate



I-15, Ontario, CA




Ramps



Chicago, IL



Brooklyn, NY



Plan View Tarrytown



Tarrytown, NY

Intersections



Rotterdam, NY - 2006



Brooklyn, NY - 2009



Complex Geometry




Replacing Existing Full Depth Asphalt



Bridge Approach Slabs



Binghamton, NY (2009)



Cross Section at Abutment



Existing Bridge



New Bridge



At the Site

- **Lay out slab locations and limits**
- **Cut and remove existing slabs**
 - May be a single or a multiple of single slabs
- **Install load transfer dowels and tie bars**
- **Place, grade and compact bedding material**
 - Mainline or ramps
- **Place slabs**
 - At specified locations
- **Install dowel and bedding grout**
- **Grind (if necessary) to achieve smoothness requirements**



Saw Cutting and Removal



**Cuts - Full Depth
- Accurate**



Slab crab bucket



**Trucks - right size
- right number**

Drilling for Dowels

**Mark Out (accurately)
to Match Dovetail Slots**



16 holes – 12 minutes



Precision Grading is the Key!

Super-Grading = Grading to 1/8th inch \pm , fully compacted

- **Thin layer (1/2") fine bedding material**
- **Grade – Compact - Grade**
- **Provides “near complete” subgrade support without grout**
- **Slabs can be opened to traffic before grouting**

Continuous Grading With Hand Operated Grader H.O.G.

THREE STEPS



First Pass (1/4" high)



Compaction




Last Pass (done)

(over 500 LF per night possible)




Grading Patches With Hand-Operated Grader (H.O.G.)

THREE STEPS
(12 minutes)



First Pass (high)



Compaction



Last Pass (done)




Placing Slabs – Continuous



Crane Occupies New Slabs



12' Lane & 10' Shoulder (min.)



Set Slab to String



Placing Slabs – Intermittent



**Center Slab in Hole
(Single Slab Holes)**



Crane Occupies New Slab



Installing Dowel Grout



Fill Dowel Slots and Joints First



Contractor-Designed Joint Dam

Installing Bedding Grout

- Mixture of Cement, Water & Admixture
 - Flow rate of 17 - 20 seconds ASTM C939
 - Must flow into thin voids
- Reaches 600 psi \pm in 12 hours
- Keep ports filled to maintain pressure



Grout In

Grout
out
(Proof)

Installed Chamber by Chamber

Keys to Success

(Still More to Learn)

Good engineering

Open minds

Real partnering

